NASECA 21st Annual Conference February, 2024



Erosion Control, Vegetation Management and Stormwater Management on the **I-39/90 Corridor Project**

Mark Polega WisDOT I-39/90 Landscape Architect WisDOT Bureau of Highway Maintenance Madison, WI

John Voorhees I-39/90 Drainage/Erosion Control Engineer AECOM, Middleton, WI







We will cover -




- Brief Project Overview
- Erosion Control Practices
- Vegetation Management along the Corridor
- Stormwater Management



In fulfillment of DNR TS4 Permit WI-S066800-2, Section 2.1.5.

Corridor **Statistics**

- Beltline Interchange in Madison to State Line at Beloit
 - Three Segments
- 2019 ADT 53,600
- 2040 ADT 65,000
- Percent Truck Traffic 28%
- Expanding from Four Lanes to Six or Eight Lanes
- Eleven Interchanges, Three of which are Diverging Diamond



Corridor **Statistics**

- 100 New Bridges
- 5 Major Creek Crossings
- 19+ Miles Reconstructed Alternative Routes
- Estimated \$1.2 Billion
- Work Began in 2012
- Construction Complete in 2022
- Contracts Completed in 2023
- Vegetation Management Complete in 2025



Erosion Control on the I-39/90 Corridor Project



- Erosion Control Fun Facts
 - 48 separate construction projects · Select Sites (waste and borrow sites)
 - 93 Commercial
 124 Private
 - Three temporary concrete batch
 - plants • 5+ culvert bypass channels
 - 10+ Dewatering systems
 - All projects required to have Soil Stabilizer Type B (Soil Stabilizing Polymer)
- Practices
 - Organic Fiber Matrix Mulch
 - Slope Interruption Compost Tubes

 - Upslope TrackingTwo-Cell Dewatering System



Organic Fiber Matrix Mulch




Special provision


 Applied on eroded steep bridge embankment with native seed

Successful slope stabilization











Upslope Tracking • Special provision, incidental • Applied to slopes longer than 30 ft. • Caltrans demonstrated significant TSS reductions (30%-60%)







39/90

IMPROVING


<u>Vegetation Management on the</u>


I-39/90 Corridor Project


Incorporating Native Vegetation Planting Using Pre-Approved Contractors

We will cover -

- Why we are doing the work
- Planting extents along the corridor
- Project contracting
- Plan/Spec development
- Construction oversight
- Lessons Learned







Corridor Planting Extents | Topolisa | Topo

Tasks


- Develop list of Pre-Qualified Contractors
- 2. Incorporate vegetation management into project plan sets
- 3. Include care cycles for each project
 - a. First year included in project
 - b. Continue with care cycles using work orders managed by Central Office
 - Second year for trees and shrubs
 - Second and third years for native seeding


First Task - Develop Approved List of Pre-Qualified Sub-Contractors


- Woody Vegetation and Native Seeding
- Contacted 430 firms statewide
 - 350 Landscape Companies
 - 80 Erosion Control Contractors
- Evaluated 11 Submittals Using Experience Criteria
 - Selected 7 Native Seeding Firms
 - Selected 6 Woody Vegetation Planting Firms
- - Company project experience
 - Scale/Scope similar to WisDOT projects
 - Available equipment
 - · Qualified herbicide applicators
 - Staff experience, work history and education


Second Task – Incorporate **Vegetation Management Plans** and Specs into Corridor Highway **Project Plans**


- · Landscape design document
- Integrate vegetation into corridor plansNative seed plant guide


























Vegetation Management Specs

- 1. Standard Spec Modifications to existing DOT spec
- 2. New Special Provisions
 - a. Topsoil Special
 - b. Compost
 - c. Subsoiling
 - d. Native Seeding Mixes
 - e. Native Seed Surveillance and Care Cycles
 - f. Pre-Planting Vegetation Treatment

Standard Spec Modifications

- Incorporated MnDOT Concepts into WisDOT Standard Plant Materials Specs
- Pre-qualified contractors to verify expertise
- Provided more detail regarding plant quality and installation
- 4. Introduced Competency Testing
- Provided more complete direction regarding care cycle performance
- Introduced inspection forms to document installation and maintenance
 - Herbicide Application
 - Tree and Shrub Scouting Report
 - Native Seed Scouting Report
 - Final Assessment of Native Plantings worksheet
 - Native Plant Survey worksheet for final site assessments

New Special Provisions

- - Added defining components Changed units to CY from SY
- Compost
- Based upon WDNR Compost Standard
- Subsoiling
 a. Two step process deep till and mixing
- b. Required multiple passes Native Seeding Mixes
- - Defined four mix types, depending upon soil and moisture conditions
 Includes both Forbes and Grasses, about 35 species
- Native Seed Surveillance and Care Cycles

 a. Describe specific care options (mowing, weeding, herbicide)
- Provide performance standards
- Requires specific documentation
- Requires seed bed preparation including herbicide application as a separate special

Third Task - Include construction oversight and care cycles for each

- 1. Provide Corridor Vegetation Inspector for project oversight and inspection
- Year 1 growing season care cycles in projects to close out projects in a timely manner
- Continue with care cycles using work orders managed by Central Office
 - Year 2 for trees and shrubs
 - Year 2 and 3 for native seeding

Nursery Stock

- Nursery Visits
- · Plant Availability
- Delivery and Inspections
- Native Species
- Plant Species Diversity
- Evergreen and Deciduous





Soils

- Variety of Soil Types some good but mostly bad
- High pH and Low Organic Content
- Modified Planting Mix During Project
- Compost
- BioChar
- Fertilizer
- · Need for Soil Testing
- · Compacted Soils









Installation

- Inspect Plant
- Plant High
- Remove top third of wire and burlap
- Fertilize
- Amend soil
- Water

Native Seed Installation Techniques

- Drill Seed Where Slopes
 Allowed
- Broadcast Utilizing Erosion Control Mat. Not great to reseed over.
- Broadcast Into Existing Thatch
- · Pro-ganic's and Miloganite
- Late Fall / Early Winter In General



Native Pollinator Friendly

- 616 Acres Planted to Prairie
- 9250 pounds of seeds
- 4 Seed Mixes Were Used
- About 35 Species
- Installed on back slopes to avoid salt contamination



Lessons Learned So Far

- Add Signs to Prevent Unwanted Mowing
- County Staff Mowing Coordination
- Add Living Snow Fence Care Cycles and Planting Process
- Highway Access
- Plant Location Field Adjustments
- Planting on Steep Slopes
- Lead Times for Tree/Shrub/Native Seed Availability and Substitutions
- Soils are Variable
- Acknowledgment of Vegetation Management Team

Stormwater Management on the





<u>I-39/90 Corridor Project</u> We will cover –

- •TMDL Requirements
- Training
- Infiltration Basins for Peak Flow Control
 - Extent
 - Subsoiling
 - Native Seeding
 - Maintenance
- Stormwater Control Practices
 - Infiltration swales and basins
 - Filter strips
 - Detention ponds

Lower Rock River TMDL


MS4	Reach Shed Num- ber	% TP Reduc- tion	% TSS Reduc-t ion
Madison	66	70.4%	72.2%
Janesville	61	N/A	40.0%
Janesville	71	57.6%	64.3%
Janesville	73	80.9%	77.5%
Janesville /Beloit	76/79	85.3%	67.9%
Beloit	81	39.3%	40.0%





MS4	Reach Shed Num- ber	% TP Reduc- tion	% TSS Reduc-t ion
Madison	66	70.4%	72.2%
Janesville	61	N/A	40.0%
Janesville	71	57.6%	64.3%
Janesville	73	80.9%	77.5%
Janesville /Beloit	76/79	85.3%	67.9%
Beloit	81	39.3%	40.0%





Training

I-39/90 Corridor Water Quality Design Requirements Training

May 31, 2013 at Southwest Region Office, Madison


 Water Quality **Design Training**

- Two training sessions (2013
- & 2014) • All Design
- Teams invited

- Introductions
 Introductions
 TSR Reduction Requirements
 Rock River TMDL
 TMDL and TRANS 401 Reduction Requirements by Reach Shed
 Detailed Corridor Maps
 ODT Stormwater Quality Analysis
 FOM Chapter 10 Sections
 FOM Chapter 10 Sections
 Fom Stormwater Report (Modified)

Janesville Infiltration Basins for Peak Flow Control - Site Plan

- Basins included to reduce ROW requirements and protect existing drainage system
- Basins designed with up to six feet dead storage volume
- Rely on infiltration to fully drain between storms
- Sand/gravel subsoils provide sufficient infiltration capacity
- Native plant root systems used to enhance infiltration
- Maintenance required to ensure proper performance





Janesville Infiltration Basins for Peak Flow Control - Subsoiling





Drangrad Subspiling Special Provision

Description his special provision describes substance rovided.	Construction as directed by the engineer or Corridor Vegeta	tion inspector, and as hereinafter	
(Vacant)	Test Plot		
C Construction Subsoil the designated area as shown in the designated area as shown in the demonstrate competence by the Vegetation inspector shall identify the subsoiled areas to a depth of 20 inches inches. After obtaining approval by the for the designated areas within the project.		or to continuing operations. The Corridor	
	Two Operations		
	corridor Vegetation ins. Deep tilling inspector's approval will be considered as u	word, complete the subsoiling operation nauthorized work.	
For the deep tilling passes, create sulfail two shanks on the equipment, with a instead create multiple channels. The equipment will be allowed. Space the	Surface mixing pass	e comprient. There shall be a minimum of	
		through previous channels, but other chisel plows, or spring-loaded occurred depth shall be to a minimum of	
20 inches. For the surface mixing pass, use a distribution operation in one pass with a commencially two tires per axie. The equipment shall be	Equipment type	too 6 to 8 inches of the soil. Do the	
		sure or to a tractor with a minimum of	
soils are saturated, delay operation: un lowed to drain freely.	the soil dries to . Disk chisel or coulter chisel	ne soil after it has been saturated and	
1 Swale and Slope Subsoiling omplete the deep tilling operation is the irection of surface drainage whenever it	eree pass. • (a Two conditions sible slopes steeper than 6 horizontal to passed at 1 february 1 feb	1 vertical (6:1), work at right angles to the	
2 Basin Subsoiling orform the deep tilling operation in	 Swale and slope subsoiling 	omolisted in either direction.	
C.3 Exceptions Area exceptions to subsoiling include areas installed, where compaction is by degral at cases where exceptions occur, observe a mile C.4 Finish Grading	Basin subsoiling	urface, when trenching/drainage lines are	
	• Exceptions dor vegetation aspector.	the Chridor Vegetation Inspector. In	
pon completion of the subsoiled and a setation inspector may be used. Discourant to the complete compl	fields grade the are • Tree drip lines 5.3.3, except that only light-weight of	uipment as approved by the Corridor solid areas that are re-compacted shall	
	Over utilities		
	Where compaction is by design		
TEM NUMBER DESCRIPTION UN			
	 Finish Grading per spec 625.3.3 		










Basin Maintenance


I-39/90 Janesville Infiltration Basin Operating and Maintenance Plan


- Basin maps and locations
- Basin feature locations

 - Drawdown sumps Sediment and water level monitoring posts

 - Inlets and outletsMonitoring wells
- Minimum infiltration requirements
- Basin performance standards
- Inspection schedule
- Vegetation maintenance requirements
- Relevant construction specifications
- Contact and Coordination
- Prepared by KL Engineering







Detention Ponds

No designed wet ponds in the corridor

- · Initial concept was to promote infiltration
- Site conditions (typically rock near the surface) sometimes restricted infiltration
- Resulting basins are all vegetated
- North Segment four dry ponds/basins
- Central Segment eighteen dry ponds/basins
- South Segment nine dry ponds/basins

Acknowledgements

- I-39 Veg Management Team
- Jenny Grimes, WisDOT Env. Coor.
- Kim Schauder, WisDOT Supervisor
- Leif Hubbard, WisDOT LA
- Mark Polega, WisDOT LA
- Christa Schaefer, WisDOT LA Michelle Inouye, AECOM LA
- Mercedez Kennedy, AECOM Insp.
- Mark Birrenkott, AECOM Eng.
 John Voorhees, AECOM Eng.
- •WisDOT Central Office/Regions
- Hans Hallanger, Stormwater Eng.
 Rodney Taylor, WisDOT Standards Eng.
- Tom Kobus, NE Region SWECE
- Jeremy Ashauer, Erosion Cont. Eng
 Peter Wisniewski, BHM Eng.
- Peter Fillipi, SW Region SWECE
- · Ann Marie Kirsch, Former Drainage Eng.

- I-39/90 Segment Design
- Consultants AECOM
- Strand
- EMCS
- OES
- KL Engineering

Acknowledgements

- I-39/90 Corridor Management
 - John Vesperman, Chief · Derek Potter, Design PM
 - Steve Marshall, Design PM
 - Mark Vesperman, Design PM
 - Mark Sponem, Const. PMAdam Kopp, Const. PM
 - E-man Yartey, Const. PM
- Jamie Grainger, Const. PM · Chad Schroeder, Const. Supr.
- DNR Liaisons/Staff
 - Shelly Nelson
 - Fric Heggelund
 - Roger Bohringer

- Construction Staff
 - · Jason Lauters, Corre
 - Doug Sina, JT
 - Jason Schrandt, Strand Tadd Owens, DAAR
 - Lance Wagner, Batterman
 - Jon Olinger, Batterman

 - · Jim Grender, CGS
 - Warren Mohar, MSA
- Contractors
 - Brian Aebly, Hoffman
 - Ryan Spies, Rock Road • Travis Giese, Hoffman
 - · Kyle Pedersen, Hoffman
 - Josh Kraemer, RES

 - Dan Fuhs, Eco Resources • Mark Remington, Stantec